K. ALL DUCT SEAMS SHALL BE SEALED.

L. ALL CEILING DIFFUSERS SHALL HAVE A MINIMUM 2'-0" LENGTH OF FLEXIBLE DUCT FOR SOUND DAMPENING. DO NOT USE FLEX DUCT TO CHANGE DIRECTION.

M. KEEP ALL DUCT OPENINGS AND AIR DEVICES COVERED AIR-TIGHT UNTIL ALL DUST CREATING ACTIVITY HAS BEEN FINISHED AND EQUIPMENT IS READY FOR START-UP.

N. DUCTWORK TO DIFFUSER SHALL MATCH DIFFUSER NECK SIZE UNLESS NOTED OTHERWISE.